SWT HYDROPOWER PROGRAM OVERVIEW

Dan Brueggenjohann

Hydropower Capital Reinvestment Program and Project Manager Programs and Project Management Div.

18 September, 2018









Discussion Topics

- Hydropower 101
- The Corps History in Hydropower
- Power Marketing Administrations (PMAs)
- Tulsa District Rehabilitation Projects
- Trends in the Hydropower Industry
- Hydropower Environment in the Future





HYDROPOWER 101

- People have a long history of using the force of water flowing in streams and rivers to produce mechanical energy.
- Hydropower was one of the first sources of energy used for electricity generation and is the largest single renewable energy source for electricity generation in the United States.
- In 2017, hydroelectricity accounted for about 7.5% of total U.S. utility-scale electricity generation and 44% of total utility-scale electricity generation from renewable energy sources. Hydroelectricity's share of total U.S. electricity generation has decreased over time, mainly because electricity generation from other sources has increased.







NOTIONAL HYDROPOWER PLANT

The first law of thermodynamics, aka Law of Conservation of Energy, states that energy can neither be created nor destroyed; energy can only be transferred or changed from one form to another



Potential \rightarrow Kinetic \rightarrow Mechanical \rightarrow Electrical \rightarrow \$\$\$\$\$







Source: U.S. Department of Energy, 2016







US Army Corps of Engineers ®

USACE HYDROPOWER

READY TODAY, WHILE SETTING THE CONDITIONS FOR FUTURE SUCCESS

– 1925 Rivers and Harbors Act

USACE authorized to explore cost and feasibility of identifying navigable rivers for power generation

– 1934 Bonneville Dam, Columbia River
First USACE project to include hydropower,
40 miles east of Portland, OR





Today

- 375 generating units at 75 dams
- 21,000 MW total capacity
- 25% of U.S. hydropower
- 3% of U.S total electric capacity
- 5th largest U.S. electric supplier
- 70 Billion KWH annually





POWER MARKETING AGNECIES (OUR PARTNERS IN HYDROPOWER)

USACE produces the power & works closely with all four DOE Power Market Administrations (PMA) across the country. PMAs have contracts to sell the power to customers, receive receipts, and send funds to the treasury.

Partners in the Hydropower Modernization Initiative

- Southwestern Power Administration (SWPA)
- Southeastern Power Administration (SEPA)
- Western Area Power Administration (WAPA)
- Bonneville Power Administration (BPA)













US Army Corps of Engineers ®



Southwestern Power Administration Region



CUTOMER FUNDING PROCESS

- A Memorandum of Agreement (MOA) was signed in 1999 by the USACE, Southwestern Power Administration, and the City of Jonesboro, AR (Southwestern Power Resource Association), to allow Southwestern customers to fund non-routine maintenance at Corps projects by diverting power receipts that would normally be returned to the treasury back to the power plant for rehabilitation.
- A collaboration among the hydropower customers, the Corps, and Southwestern allows the prioritization of maintenance to provide the greatest benefit.
- To date, 135 Sub-agreements have been executed to perform work in Tulsa District.
- The total amount approved for funding is approximately \$360M.





Tulsa District Hydropower

LOCALLY, SWT: **Eight (8) Plants:** Texoma- 1949 2 units- 70 MW Eufaula-1965 3 units- 90 MW Ft Gibson- 1953 4 units- 50 MW Keystone-1968 2 units- 70 MW Tenkiller- 1954 2 units- 39,1 MW **RS Kerr- 1971** 4 units- 110 MW Broken Bow- 1970 2 units- 100 MW Webbers Falls- 1974 3 units- 60 MW

Texas

Optima

ake

Beaver

imaron R



Approx. 600 Megawatts of capacity **Customers are Rural Electric Coops**





HYDROPOWER PLANT REHABILITATION



TULSA DISTRICT TURBINE/GENERATOR PROJECTED TIMELINES AND PROGRAM ESTIMATE

Year																											
Projects	2016	2017	2018	2019	2020	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030	2031	2032	2033	2034	2035	2036	2037	2038	2039	2040	2041	2042
Webbers Falls Rehabilitation	\$85M																										
Denison Turbine		\$50																									
Replacement		Μ																									
RS Kerr																											
Rehabiltation																											
Keystone																											
Rehabilitation										\$54N	Л +																
Eufaula																											
Rehabilitation									\$54M+																		
Tenkiller																											
Rehabilitation															\$30M+												
Fort Gibson																											
Rehabilitattion															\$36M+												
Broken Bow																											
Rehabilitation																							\$40M+				

Cost for turbine/generator; Does not include balance of plant.





Webbers Falls Major Rehabilitation

- Project Scope: Replace three turbines, rewind three generators and rehabilitate all cranes, tailrace and intake gates and bulkheads.
- Total Project cost, including turbines, generator, gates, cranes, governors and misc: \$88.2M (\$83.8M customer funded)
- 2 MW per unit (8.5%) increase by up-rating.
- Anticipated Turbine Completion Date: 19 September 2018
- Commence Rewind of the last generator October 2018





POWERHOUSE CUTVIEW



NEW RUNNER DESIGN





KAPLAN RUNNER CONFIGURATION OLD VS. NEW









GATE BARREL REMOVAL















WICKET GATES









RUNNER INSTALLATION











rps 's ®

LOWER MAIN SHAFT







INTERMEDIATE SHAFT









US Army Corps of Engineers ®



DENISON TURBINE REPLACEMENT SCOPE AND BUDGET

- Project Scope: Replacement of two francis turbines, installation of new digital governors, gas insulated 3 phase transformers, switchgear, bus and rehabilitation of the bridge crane.
- Turbine efficiency increase from 40 MW to 50 MW
- Total Customer Funding \$50,295,000



DENISON 1944 CONSTRUCTION



DENISON 2018 – TURBINE REPLACEMENT



Denison Rotor Removal









US Army Corps of Engineers ®

Old Runner Removal/New Runner Delivery









Removed on 2 Feb 2018

Inner Head Cover (Bearing Housing) Condition

















R. S. Kerr Major Rehabilitation

Scope, Cost and Agreements

- Replace four Kaplan turbines, rewind four generators, refurbish governors and exciters, rehabilitate bridge and intake crane, replace tail race crane, replace transformers, rehabilitate draft tube and roller gates and construct new roller gate and draft tube gates.
- Energy Output 36MVA/unit
- Total Project Cost: \$192,144,000

R. S. Kerr Major Component Award Schedule

- New Draft Tube Crane Award 6 Dec 2018
- Transformer Award 2 Dec 2018
- Bridge Crane Rehab Award 15 Dec 2018
- Modernization of Electrical Infrastructure Award – 28 Mar 2019
- New Gates and Bulkhead Award 7 Mar 2019
- Exisiting Gates and Bulkhead Minor Repair Award – 7 Mar 2019
- Turbine & Generator Award 26 Oct 2019



R. S. Kerr Turbine Generator Schedule

Turbine Generator Design Completion: 16 July 2018 Turbine Generator Contract Award: 26 Oct 2019 Model Test, Design, and Fabrication: Jan 2019 to Dec 2020 Unit 1 Construction Period: 26 Oct 21 to 26 Sep 2022 Unit 2 Construction Period: 26 Sep 2022 to 25 Oct 2023 Unit 3 Construction Period: 25 Oct 2023 to 24 Oct 2024 Unit 4 Construction Period: 24 Oct 2023 to 24 Oct 2025







29

HYDRO TRENDS TODAY

- Unit and Plant optimization
- New Technologies/Digital Equipment
- Cyber Protection, GDACS/SCADA, Instrumentation for the Corps & Others
- Renewable Energy Integration
- Investing in Modernization/Rehabilitation of our Infrastructure



THE HYDROPOWER ENVIRONMENT IN THE NEXT 30-50 YEARS

- High Certainty of increasing Large Capital Investment to Remodernize Corps' hydropower fleet.
- High value energy resource; Base, Peak, Voltage Support, Frequency Response/Regulation, major integrator of other renewables
- Increased Emergency Response, Aging Fleet, Forced Outages, Trouble shooting, Emergency Repairs, Forensics
- SCADA & Industrial Control System Emerging Requirements, Compliance and Reliability burden, cyber security assurance





Questions ?



